

**Town of Salem NH  
Fire Department  
Foundation for Antenna Tower  
BID (2019-032)**

**Addendum No. 2  
November 26, 2019**

The following questions have been posed to Fire Marshall Jeff Emanuelson by email since the release of this BID. Answers are provided in **bold RED** font.

1. Is the town approving the use of existing material for backfill or does new structural material need to be brought in for over the foundation? **Specification calls for crushed gravel base. Existing material on site can be used for backfill if it can be prepared properly.**
2. Whether or not material is reused there will be left over material from the excavation. How will it be handled? **Town will dispose of excess material.**
  - A. **left stock piled next to the tower for town to deal with**
  - B. Be loaded into town trucks during the excavation process to be taken way
  - C. The contractor will be responsible for the loading and disposal in an area approved by the town for no fee.
  - D. The contractor will be responsible for the loading and disposal material off site.
3. How will the backfilled excavation and stockpile area be left? Rough graded? **Yes, rough graded.**